

CONFIDENTIAL

TENDER NO:



COUNTY GOVERNMENT OF KERICH

**DEPARTMENT OF WATER,ENERGY,ENVIRONMENT,FORESTRY AND NATURAL
RESOURCES.**

TENDER DOCUMENT

BILLS OF QUANTITIES

FOR

**PROPOSED REHABILITATION AND IMPROVEMENT OF KAPSOIT WATER SUPPLY
PROJECT ,KAPSOIT WARD.**

WATER WORKS

AT

AINAMOI SUB-COUNTY.

Prepared By:

The County Water Engineer,
Department of Water,Energy,Environment,Forestry and Natural Resources,
P.O Box 112-20200,
KERICH, KENYA.

Issued By:

NOVEMBER 2024

PROPOSED REHABILITATION AND IMPROVEMENT OF KAPSOIT WATER SUPPLY PROJECT

Item	Description	Quantity	Unit	Rate	Amount
	<u>BILL NO. 01</u> <u>PRELIMINARIES AND GENERAL CONDITIONS.</u>				
A	Provide, erect, maintain and remove on completion of the project a sign board as directed by the Engineer	item	3	20,000	60,000
B	Allow a Provisional sum of kshs. 430,000 only for Project Supervision and Management to be used as per the Engineers instructions	PC	1	430,000	430,000
C	20% Profits from item B	%	0.2	430,000	86,000
	Carried to Summary				576,000.00
	<u>BILL NO. 02</u> <u>PIPEWORK.</u>				
	Provide, lay, joint and test the following pipes and fittings. Rates to include for all jointing materials, fittings, cuttings, wastages and anchorage.				
A	Desilk line HDPE 32mm PN 16	LM	700		
B	Mimosa dispensary - Kapkitony ECD Line HDPE 63mm PN 16	LM	600		
C	HDPE 50mm PN 16	LM	900		
D	HDPE 32mm PN 16	LM	300		
E	Cheptingting Upper & Lower Line HDPE 63mm PN 16	LM	100		
F	HDPE 50mm PN 16	LM	500		
G	HDPE 32mm PN 16	LM	1400		
H	To Kapibatt HDPE 90mm PN 16	LM	800		
I	Kenegut junction - Kapsisiwo - Chepkoinik HDPE 63mm PN 16	LM	1000		
J	HDPE 50mm PN 16	LM	1000		
K	Sitotwet - Chemobei HDPE 63mm PN 12.5	LM	2600		
L	HDPE 32mm PN 16	LM	400		
M	Kosisit - Kiboybei - Kenegut HDPE 75mm PN 16	LM	5300		
N	HDPE 50mm PN 16	LM	1000		
O	HDPE 32mm PN 16	LM	3000		
P	Allow 15% for assorted pipe fittings (connectors) of items A to O above	%	0		
Q	Provide and install assorted sizes of gate valves as peglar with all necessary fittings	No	17		

R	Provide and install Sectional air valves with all necessary fittings as Instructed by the Engineer.	No	8		
S	Provide the necessary materials and construct 1x1x1m Masonry valve chambers	No	25		
	Carried to Summary				
	BILL NO. 03				
	EXCAVATION.				
	Rates for excavation and backfilling trenches, shall include for trimming trench bottom, providing selected bedding and surround material from the excavations as directed by the Engineer.				
A	In normal soil to receive pipes. Pipeline depth not less than 0.6m and not exceeding 1.5m.	CM	3292.8		
B	Ditto to Hard ground.	CM	2195.2		
	Carried to Summary				

COUNTY GOVERNMENT OF KERICHO					
DEPARTMENT OF WATER,ENERGY,ENVIRONMENT,FORESTRY AND NATURAL RESOURCES.					
PROPOSED REHABILITATION AND IMPROVEMENT OF KAPSOIT WATER SUPPLY PROJECT					
GRAND SUMMARY					
BILL NO	DESCRIPTION				AMOUNT
1	PRELIMINARIES AND GENERAL CONDITIONS.	<u>From Page</u>			576,000.00
2	PIPEWORK				
3	EXCAVATIONS				
	SUB TOTAL				
	16% VAT				
	TOTAL CARRIED TO FORM OF TENDER (Amount inclusive of 16% VAT & Withholding Tax)		Kshs.		
	AMOUNT IN WORDS (Amount inclusive of 16% VAT and Withholding Tax) Contractor's Official Rubber Stamp Name of Witness Contractor's Signature Address Of Witness Date: Date: 				