

CONFIDENTIAL

TENDER NO:



COUNTY GOVERNMENT OF KERICHIO
DEPARTMENT OF FINANCE AND ECONOMIC PLANNING.

TENDER DOCUMENT

BILLS OF QUANTITIES

FOR

**SUPPLY, INSTALLATION, TESTING AND COMMISSIONING OF A MODERN
MAIZE MILLING PLANT, KEDOWA /KIMUGUL WARD.**

AT

KIPKELION EAST SUB COUNTY.

Prepared By:

The County Quantity Surveyor,
Department of Lands Housing and Physical Planning,
P.O Box 112-20200,
KERICHO, KENYA.

Issued By:

MARCH 2025

Item	Description	Quantity	Unit	Rate	Amount
	BILL NO. 01				
	MAIZE MILLING PLANT				
	Supply, Install, Test and Commission a Modern Maize Milling Plant, with the following specifications: One Set of 2500KG/H Maize milling machine with spares				
1.1	Roller Mill (4 Pairs of Rolls, Stainless Steel)	1	Set		
1.2	Plansifter (6 Sieves, 12.5m² Sieve Area)	1			
1.3	Degerminator (Carbon Steel, 4 kW)	1			
1.4	Spare Parts (Belts, Bearings, Rollers)	1	Set		
2	One Set of Combined Cleaning Machine with Damping Machine				
2.1	Vibrating Separator (Stainless Steel)	1			
2.2	Destoner (Carbon Steel, 1.5 kW)	1			
2.3	Magnetic Separator (3000-5000 Gauss)	1			
2.4	Air Suction Separator (1,250 m³/h)	1			
2.5	Maize Conditioner (2 Kw, Stainless Steel)	1			
3	One set of Packaging Equipment				
3.1	Automatic Weighing & Packing Machine (0.5-50 kg)	1			
3.2	Sealing Machine (Stainless Steel, 0.5 kW)	1			
4	One set of Handling Equipment				
4.1	Screw Conveyor (Stainless Steel, 2 Tons Per Hour)	1			
4.2	Bucket Elevator (Carbon Steel, 2 Tons Per Hour)	1			
5	One set of Blending and Fortification				
5.1	Blending System (Stainless Steel, 0.8 kW)	1			
5.2	Fortification Doser (12.5 kg/hr, ±0.5% Accuracy)	1			
6	One Set of Auxiliary Equipment				
6.1	Air Compressor (1.25 m³/min, 8 Bar)	1			
6.2	Dust Collection System (2500 m³/h, 4 kW)	1			
6.3	Control Panel (PLC-Based, Touchscreen Interface)	1			
7	Installation, Commissioning & Training				
7.1	Mechanical & Electrical Installation	1			
7.2	Commissioning & Testing	1			
7.3	On-site Training (2 Weeks)	1			
	Total For Maize Milling Plant Carried to Summary			Kshs	

Item	Description	Unit	Amount
A	<u>BILL NO. 02</u>		
	<u>PRIME COSTS, PROVISIONAL & CONTINGENCY SUMS</u>		
	<u>Project Management</u>		
	Allow a Provisional Sum of Kenya Shillings Two Hundred and Fifty Thousand Only (Kshs. 250,000.00) for Project Management.	Sum	250,000.00
TOTAL FOR PROVISION AND PC SUMS CARRIED TO SUMMARY			250,000.00

COUNTY GOVERNMENT OF KERICHO					
DEPARTMENT OF FINANCE AND ECONOMIC PLANNING.					
SUPPLY, INSTALLATION, TESTING AND COMMISSIONING OF A MODERN MAIZE MILLING PLANT, KEDOWA /KIMUGUL WARD.					
GRAND SUMMARY					
BILL NO.	DESCRIPTION				AMOUNT
1	Modern Maize Milling Plant				
2	Prime Costs & Provisional Sums				250,000.00
	TOTAL CARRIED TO FORM OF TENDER (Amount inclusive of 16% VAT & Withholding Tax)		Kshs.		
	AMOUNT IN WORDS (Amount inclusive of 16% VAT and Withholding Tax) Contractor's Official Rubber Stamp Name of Witness Contractor's Signature Address Of Witness Date: Date: 				